

Barnes Lumber Redevelopment

5-May-14

Stormwater Management Block Plan

	Proposed Stormwater Management Measures	Alternate Stormwater Management Measures	Drainage Outfall Location
Block 1	Manufactured BMP, Underground Detention	Bioretention	West (connect into Library Ave. system)
Block 2	Manufactured BMP, Underground Detention	Bioretention/ Infiltration	Southeast corner of site
Block 3	Manufactured BMP, Underground Detention	Bioretention/ Infiltration	Southeast corner of site
Block 4	Wet Pond/Extended Detention	Bioretention/Manufactured BMP	Southeast corner of site
Block 5	Wet Pond/Extended Detention	Bioretention/Manufactured BMP	Southeast corner of site
Block 6	Rooftop Disconnection, Grass Swale, Wet Pond/Extended Detention	Bioretention/Manufactured BMP	Southeast corner of site
Block 7	Wet Pond/Extended Detention	Bioretention/Manufactured BMP	Southeast corner of site
Block 8	Wet Pond/Extended Detention	Bioretention/Manufactured BMP	Southeast corner of site

Note: This chart and the precedent images attached are for illustrative purposes only to show what types of SWM measures may be implemented. They are not proffered by the applicant.